

2009 Salt Lake Countywide Water Quality Stewardship Plan

ADDENDUM STREAM FUNCTION INDEX Taylorsville City Report



**2009
SALT LAKE COUNTYWIDE
WATER QUALITY STEWARDSHIP PLAN**

**ADDENDUM
STREAM FUNCTION INDEX REPORT**

Taylorsville Report

PREPARED BY:

**Flood Control and Water Quality Division
Salt Lake County
2001 South State Street
Suite N3100
Salt Lake City, UT 84190**

April 2010

Printed on 10% Recycled Paper
Elemental Chlorine-Free (ECF)
FSC Certified (mixed sources)



This page intentionally blank.

TABLE OF CONTENTS

1.0	Introduction	1
1.1	Components of the Stream Function Index (SFI) and Ecosystem Health Index (EHI).....	1
1.2	Data Collection.....	1
2.0	Taylorsville City—Information	3
2.1	Water Quality Stressors in Taylorsville City.....	3
3.0	Stream Function Index (SFI)	4
4.0	Watershed Function Groups	4
4.1	Water Quality Functional Group Score	4
4.2	Habitat Functional Group Score.....	6
4.2.1	Pool/Riffle Ratio in Taylorsville City	7
4.2.2	Water Depth in Taylorsville City.....	8
4.2.3	Fish Passage in Taylorsville City	9
4.2.4	Habitat Structure in Taylorsville City.....	10
4.2.5	Flow Diversion in Taylorsville City	11
4.2.6	Riparian Width in Taylorsville City	12
4.2.7	Riparian Density in Taylorsville City	13
4.3	Hydraulics Functional Group Score	14
4.3.1	Floodplain Development in Taylorsville City.....	15
4.3.2	Floodplain Connectivity in Taylorsville City.....	16
4.3.3	Hydraulic Alteration in Taylorsville City.....	17
4.3.4	Bank Stability in Taylorsville City	18
4.4	Social Functional Group Score	19
5.0	Ecosystem Health Index (EHI) - Taylorsville City	20
6.0	Stream Function Index (SFI) - Taylorsville City	21
7.0	Implementation	22
7.1	Site Identification.....	22
7.2	Plan Development.....	22
7.3	Funding	22
7.4	Plan Implementation	23
7.5	Post Construction.....	23

LIST OF FIGURES

1	Water Quality Functional Group Scores Countywide	5
2	Habitat Functional Group Scores Countywide	6
3	Habitat Function—Pool/Riffle Ratio in Taylorsville City	7
4	Habitat Function—Water Depth in Taylorsville City.....	8
5	Habitat Function—Fish Passage in Taylorsville City	9
6	Habitat Function—Habitat Structures in Taylorsville City	10
7	Habitat Function—Flow Diversion in Taylorsville City	11
8	Habitat Function—Riparian Width in Taylorsville City	12
9	Habitat Function—Riparian Density in Taylorsville City.....	13



WATER QUALITY
STEWARDSHIP PLAN

Salt Lake County—Stream Function Index (SFI) Taylorsville City

10	Hydraulics Functional Group Scores Countywide	14
11	Hydraulics Function—Floodplain Development in Taylorsville City	15
12	Hydraulics Function—Floodplain Connectivity in Taylorsville City	16
13	Hydraulics Function—Hydraulic Alteration in Taylorsville City	17
14	Hydraulics Function—Bank Stability in Taylorsville City	18
15	Social Functional Group Scores Countywide	19
16	Ecosystem Health Index (EHI) Final Score 2009	20
17	Stream Function Index (SFI) Final Score 2009	21
18	Diagram of Emergent Bench Design	22

LIST OF TABLES

1	Stream Function Index Metrics Flow Chart	2
2	Taylorsville City Watershed Areas and Stream Lengths	3
3	Grants for Stream and river Restoration Projects.....	24

1.0 INTRODUCTION

Armed with the widely supported 2009 Salt Lake Countywide Water Quality Stewardship Plan (WaQSP), regulatory and municipal authorities in Salt Lake County seek to work collaboratively to monitor and improve watershed and stream health. After examining the current conditions, numerous water quality and watershed improvement recommendations were made in the 2009 WaQSP. However, written recommendations and well laid plans are only as good as the implementation efforts that result. With the completion of the WaQSP, Salt Lake County and its partners now enter the most challenging and rewarding phase of watershed management—implementation. A key challenge in the implementation phase is to measure the success and/or failure of implementation efforts. Therefore, to inform future planning decisions, and to assure a successful, iterative, planning and implementation process, Salt Lake County developed a monitoring tool for the WaQSP known as the Stream Function Index (SFI). The SFI was developed in 2006 with the assistance of several environmental consulting firms. The primary consultant on this effort was Cirrus Ecological, based in Logan, UT.

It is anticipated that SFI data will be collected along with each update of the WaQSP that will occur every six years. It is also anticipated that reports, such as this one, will be written for each municipal government at that same frequency. Successful implementation of WaQSP recommendations should lead to improved SFI scores. However, if BMPs do not lead to improved SFI scores, they will be re-examined for effectiveness in the local environment.



Jordan River along eastern boundary of Taylorsville.

1.1 COMPONENTS OF THE STREAM FUNCTION INDEX (SFI) AND ECOSYSTEM HEALTH INDEX (EHI)

Streams and rivers, although single components of the larger watershed, may serve as indicators of overall watershed health. To maximize resources and time, Salt Lake County decided to focus on monitoring stream and river corridors to indicate overall watershed function. However, a broader examination of watershed function may be accomplished in the future with increased funds and staff. For the purposes of this document, data collected in stream and river corridors are used to indicate watershed function.

To monitor stream and river health, the SFI measures physical, chemical, biological, and social functions of stream and river corridors in Salt Lake County. The four watershed functions that are examined in the SFI include: habitat (aquatic and terrestrial), hydraulics (flood conveyance and stream stability), water quality and social (recreation and aesthetics). Metrics used to determine scores for each of the four watershed functions are included in Table 1. Recreation and aesthetics monitoring is included in the SFI to indicate the degree to which stream and river corridors provide appropriate, or resource compatible, recreation and aesthetic opportunities. However, recreational facilities may, if incompatible with the resource, detrimentally effect stream ecology.

In order to examine ecological health independent of social function, Salt Lake County created an Ecological Health Index (EHI). The EHI is a sub-component of the SFI that includes habitat, hydraulics, and water quality evaluations. The EHI may be compared with the SFI to determine possible effects of social (i.e. recreational and aesthetic) functions on stream ecology.

See the “Stream Function Index Main Report” Appendices for the complete SFI Methodology Report.

1.2 DATA COLLECTION

The majority of 2009 SFI numbers were based on data gathered between 2007 and 2008. However, water quality data spans a greater time period (2001 to 2008). In future SFI updates, it is anticipated that water quality data collected between updates will be used to assess stream health. Although previous stream stability and fish



Salt Lake County—Stream Function Index (SFI)
Taylorsville City

Metric	Sub-Group	Functional Group	Ecosystem Health Index	Stream Function Index
Pool/Riffle ratio	Stream Channel	Habitat	EHI	SFI
Water Depth				
Fish Passage				
Habitat Structures				
Flow Diversion				
Riparian Width				
Riparian Density	Riparian Corridor			
Floodplain Development	Flood Conveyance	Hydraulics		
Floodplain Connectivity				
Bank Stability	Stream Stability			
Hydraulic Alteration				
303(d) list	Regulatory	Water Quality		
Macroinvertebrate	Aquatic			
Total P	Monitoring			
Temperature				
TDS				
DO				
<i>E. coli</i>				
Management	Aesthetics	Social		
Visual Aesthetics				
Location	Amenities (Nodes)			
Accessibility (ADA Approved)				
Restrooms				
Resource Compatibility (Nodes)				
Trail Corridor	Amenities (Trails)			
Connectivity				
Resource Compatibility (Trails)				

Table 1. Stream Function Index Metrics Flow Chart

habitat assessments were conducted on a few streams and the Jordan River in the mid 1980's, the 2009 SFI represents the first comprehensive assessment of all major waterways in Salt Lake County. Therefore, this dataset is considered a baseline.

The SFI is intended to give watershed and stream managers an overview of current stream conditions. However, as improvement projects are identified, more detailed studies may be required to fully assess the condition of the stream.



Taylorsville residents cooling off in the Jordan on a hot summer day.

2.0 TAYLORSVILLE CITY - INFORMATION

Taylorsville City, located in the west central portion of Salt Lake County, is a relatively new city (incorporated in 1996) and is home to approximately 58,035 residents. Contained within Taylorsville's boundaries are portions of four sub-watersheds: Lower Big Cottonwood Creek, Barney's Creek, Decker Lake, and Jordan River Corridor. Additionally, a section of the Jordan River runs along Taylorsville's east boundary. This report summarizes the health of the river and stream sections within Taylorsville City and provides guidance for future water quality improvement and watershed preservation efforts. Taylorsville City will also receive a copy of the 2009 WaQSP Addendum Stream Function Index Main Report, and will receive electronic files of the report and Geographic Information System (GIS) shapefiles depicting information collected as part of the SFI.



Jordan River along the eastern boundary of Taylorsville.

2.1 WATER QUALITY STRESSORS IN TAYLORSVILLE CITY

Although the SFI is a measure of stream corridor health, it is imperative that water quality and watershed health be approached comprehensively. Therefore, this section is provided to review water quality stressors identified in the 2009 WaQSP for the sub-watersheds in Taylorsville City.

As part of the 2009 WaQSP, a computer-based GIS analysis was conducted for each of the 27 sub-watersheds in Salt Lake County to determine existing and potential future water quality stressors. In Chapter 5 of the WaQSP document, these water quality stressors are outlined and

Best Management Practices (BMPs) recommended to address potential concerns. Below are examples of water quality stressors and associated BMPs. To determine water quality stressors identified in sub-watersheds that intersect Taylorsville City boundaries, please consult the 2009 WaQSP.

Water quality stressors may include:

- Stream channel modification
- Lack of developed recreation
- Stream flow diversions
- Loss of open space
- High number of Industrial Stormwater Discharge Permits
- Floodplain encroachment
- Densification of residential land use
- Urban development and redevelopment pressures

Examples of Management Practices (BMPs) to address potential water quality stressors include:

- Bioengineered bank stabilization
- Grade control structures

Taylorsville City		6,008 Acres
Sub-Watersheds	Lower Big Cottonwood Creek	<1 Acres
	Barney's Creek	5,131 Acres
	Decker Lake	83 Acres
	Jordan River Corridor	1,740 Acres
Streams	Jordan River	17,350 Feet

Table 2. Taylorsville City Watershed Areas and Stream Lengths



Salt Lake County—Stream Function Index (SFI) Taylorsville City

- Channel restoration/enhancement
- Streambank revegetation
- Diversion structures modification
- Canal water diversion
- Leadership in Energy and Environmental Design criteria
- Minimum flow protection
- Water rights acquisition
- Identify community recreation needs and opportunities
- Wetlands restoration/enhancement
- Manufactured treatment systems
- Participate in new and/or existing planning efforts
- Floodplain re-establishment
- Trash racks
- Land acquisition for preservation
- Volunteer programs
- Recreational facilities that are accessible and resource compatible.



Trail underpasses and pedestrian bridges along the Jordan River Parkway allows access to the river for Taylorsville residents.

3.0 STREAM FUNCTION INDEX (SFI)

Similar to the 2009 WaQSP effort to identify water quality/watershed stressors, four watershed functions were examined for each stream: water quality, habitat, hydraulics, and social/aesthetics services. In order to assess the ability of streams to provide these four functions, Salt Lake County developed what is called the Stream Function Index (SFI). The SFI is a rapid assessment

protocol that assesses stream habitat, hydraulics, water quality and social factors. Based on established methodology, the SFI measures 27 metrics to determine overall stream health. These metrics are categorized by watershed function (water quality, habitat, hydraulics, social/aesthetic) and can therefore be examined individually or by functional group.

The SFI is a tool to help identify the results of water quality stressors along main stream channels and the Jordan River. These areas are candidates for enhancement projects. The SFI provides the framework for a more detailed baseline and monitoring techniques that may be used on those projects. The first complete dataset was collected during the 2007 and 2008 field seasons and is considered the baseline. The SFI will be repeated every 6 years in conjunction with the Water Quality

4.0 WATERSHED FUNCTION GROUPS

This section summarizes scores for the four watershed functions countywide and reviews data and scores within Taylorsville City boundaries. Additional information on SFI methodology can be found in the SFI Main Report.

4.1 WATER QUALITY FUNCTIONAL GROUP SCORE

The SFI water quality functional group is comprised of seven metrics or measures: 303(d) list status, Macroinvertebrates, Total Phosphorus, Temperature, Total Dissolved Solids (TDS), Dissolved Oxygen (DO), and Coliform (*E. Coli*). Based on 2009 SFI scores, the streams with the best water quality are concentrated in the upper regions of both the Wasatch and Oquirrh streams, with the notable exception of upper Little Cottonwood Creek (currently listed as water quality impaired by the State Division of Water Quality) for zinc. Additionally, lower Emigration Creek and Red Butte Creek received high rankings for water quality. Notably, these scores are based entirely on data contained in the Environmental Protection Agency's STORET database. Although this data represents a large portion of water quality data collected in Salt Lake County, it does not represent all data. However, it was decided that the SFI would rely on STORET data to assure consistent methodologies and that certified water quality assurance (QA) and water quality control (QC) measures were taken.

Salt Lake County—Stream Function Index (SFI)
Taylorsville City




Figure 1. Water Quality Functional Group Scores Countywide

In addition to noting areas of high, or good, water quality, it is important to note areas of low, or poor water quality. As can be seen from the Countywide data presented in Figure 1., segments with low water quality values include: upper and lower Jordan River, lower and upper Little Cottonwood Creek, lower Big Cottonwood Creek, and upper Emigration Creek. All of these segments scored as meeting water quality standards in <50% of samples taken. Many of these water quality concerns are currently being addressed through the State Division of Water Quality's (DWQ) Total Maximum Daily Load (TMDL) program.

Water quality concerns in Taylorsville City are focused on the Lower Jordan River. Pollutants of

concern include Total Dissolved Solids (TDS), temperature, Dissolved Oxygen (DO), and *E. Coli*. In order to address these concerns, it is recommended that Taylorsville City actively participate in the Jordan River TMDL process by attending Jordan River Watershed Council (JRWC) meetings and reviewing documents that are published in conjunction with the Jordan River TMDL.



Salt Lake County—Stream Function Index (SFI) Taylorsville City




Figure 2. Habitat Functional Group Scores Countywide

4.2 HABITAT WATERSHED FUNCTION

In the SFI, the habitat function was characterized by: pool/riffle ratio, fish passage, habitat structure, flow diversion, riparian width, and riparian density. Of note, stream channel habitat metrics were only assessed for streams that have been identified, by the State Division of Wildlife Resources (DWR) as support fish habitat. Flow diversion and riparian metrics were assessed for all streams.

Similar to the Water Quality Functional Group Score, streams with the best, or highest scores, are concentrated in the upper regions of both the Wasatch and Oquirrh mountains. However, in contrast to water quality, not all sections of upper Oquirrh Mountain streams rank high for habitat. Of

note, Copper Creek and Rose Creek both scored <60% for overall habitat function. Other areas of particular habitat concern include lower Big and Little Cottonwood Creeks and the section of Butterfield Creek upstream from its confluence with Midas Creek.

As can be seen from Figure 2, Taylorsville City contain sections of the Jordan River that received overall habitat function scores between 50 and 59.9. Recommendations to improve habitat function in the Jordan River should be coordinated with adjacent municipal governments, State agencies, and Salt Lake County Flood Control Division and will be further explored in the following sections that examine specific habitat concerns.




Figure 3. Habitat Function—Pool/Riffle Ratio in Taylorsville City

4.2.1 Pool/Riffle Ratio in Taylorsville City

An important component of stream habitat function is the ratio between pools and riffles. For the SFI, the number of pools and riffles were counted for each stream reach. Pools were defined as mid-channel areas with low velocity that were at least 1 foot deep. Riffles were defined as mid-channel shallow turbulent areas of higher velocity. The number of pools was compared to the expected number for the given stream type (see SFI Main Report for an explanation of stream type.) Subsequently, the pool/riffle ratio was determined. A score of “Not Applicable” (N/A) indicates that the stream does not support a fishery.

The majority of the Jordan River section within the Taylorsville City boundary scored between 26 and 50 for pool/riffle ratios (Figure 3). However, the lower section within Taylorsville City scored lower (between 1 and 25). These scores may be largely due to the wide, shallow, low gradient nature of the Jordan River within this section of the Jordan River. Therefore, recommended actions to improve pool/riffle ratio include: participating in river restoration projects that incorporate habitat enhancement measures to improve pool/riffle ratio. Because the gradient in this section of the Jordan River is extremely low, efforts to improve pool/riffle ratio will most likely focus on channel geometry.

Salt Lake County—Stream Function Index (SFI)
Taylorsville City




Figure 4. Habitat Function—Water Depth in Taylorsville City

4.2.2 Water Depth in Taylorsville City

In Salt Lake County, many streams have experienced altered or reduced stream flow or may naturally have minimal stream flow. In order to assess the extent to which streams have sufficient water depth to support aquatic habitat, Salt Lake County staff measured stream depth at representative locations within each stream reach during late summer low flow. Targets for this metric were set based on minimum depth requirements for trout and native sucker species established by the Utah Division of Wildlife Resources (DWR).

As can be seen in Figure 4, the section of the Jordan River within Taylorsville City boundaries ranked high for water depth (100). Although the

flow through this section of the Jordan River is highly altered, the remaining water depth appears sufficient to support fish habitat. Therefore, no immediate action is required for this metric; however, it is recommended that Taylorsville City monitor any water right activities that may alter water depth within this section of the Jordan River and seek to sustain existing water depths.

Salt Lake County—Stream Function Index (SFI)
Taylorsville City




Figure 5. Habitat Function—Fish Passage in Taylorsville City

4.2.3 Fish Passage in Taylorsville City

For the purposes of the SFI, fish passage was scored based on the distance between barriers to fish passage. Barriers were tallied for each stream reach and analyzed for overall function during late summer low flow. Barrier criteria included height of barrier, depth of plunge pool, water depth, and beaver dam density. The optimum value for this metric was to have at least 1/4 of a mile between barriers.

alteration permit requests proposals to assure that fish passage is sufficiently accommodated in these plans.

As can be seen from Figure 5, the section of the Jordan River that borders Taylorsville City received a high score for fish passage (100). Therefore, no immediate action is recommended for this metric. However, it is recommended that Taylorsville City closely monitor any future stream



Salt Lake County—Stream Function Index (SFI) Taylorsville City




Figure 6. Habitat Function—Habitat Structures in Taylorsville City

4.2.4 Habitat Structure in Taylorsville City

For the purposes of the SFI, habitat structures are defined as in-stream natural, or man-made, objects that provide cover, resting, and feeding resources for fish species. To measure the function of habitat structures, the number of embedded logs, rootwads, boulders, undercut banks, beaver dams, and man-made structures were tallied for each reach. Targets were set based on the number of habitat structures anticipated to occur in specific stream types.

As can be seen from Figure 6, the majority of the Jordan River section within Taylorsville City boundaries scored 0 for habitat structure. The lower section of the Jordan River in Taylorsville City scored slightly higher (between 26 and 50) for this metric.

Recommended actions to improve habitat structure resources in Taylorsville City include: participating in river restoration projects that incorporate habitat enhancement measures, participate in discussions regarding opportunities to accommodate flood control, water rights, recreation, and habitat needs. As with many metrics, habitat structures are essential to stream function, but need to be balanced with other stream functions.

Salt Lake County—Stream Function Index (SFI)
Taylorsville City



WATER QUALITY
STEWARDSHIP PLAN




Figure 7. Habitat Function—Flow Diversion in Taylorsville City

4.2.5 Flow Diversion in Taylorsville City

In the arid environment of Salt Lake County, many streams have been greatly impacted due to altered surface and groundwater flows. To include potential effects on habitat in the SFI, Salt Lake County developed a flow diversion metric. The flow diversion metric measured the degree to which natural surface stream flows have been reduced or interrupted. This metric includes both the amount of time over a year and the length of stream that is maintaining natural flows. The target for this metric was set at 100%, i.e. a natural flow for 100% of the year.

diversion (0). As individuals familiar with the Jordan River will know, there are seven major canal diversions on the upper Jordan River that are used to convey irrigation water. Of note, the 2009 WaQSP document calls for a comprehensive review of Jordan River flow management.

It is recommended, that Taylorsville City participate in any discussions that may be facilitated by the JRWC or the State Engineer’s office to examine flow management of the Jordan River.

As can be seen in Figure 7, the section of the Jordan River adjacent to Taylorsville City’s boundaries scored extremely poorly for flow

Salt Lake County—Stream Function Index (SFI)
Taylorsville City




Figure 8. Habitat Function—Riparian Width in Taylorsville City

4.2.6 Riparian Width in Taylorsville City

The SFI also examined habitat beyond the stream channel with Riparian habitat metrics. The first metric examined was the width of riparian corridors. For the purposes of the SFI, riparian width was measured as the continuous and contiguous areas of uninterrupted vegetation growth along streams. The target riparian width was established by Salt Lake County to be 100 feet, i.e. ideally, all streams/river in the County would be bordered on both sides by 100 feet of uninterrupted vegetative growth. The actual amount of riparian vegetation was then compared with the target.

scored between 26 and 99 for riparian width with the higher scores (between 76 and 99) between 3800 South and 5400 South.

To improve riparian habitat function of the streams and river in Taylorsville City, it is recommended that: the City pass a land use ordinance to limit development within 100 feet of streams and river (this may also be included in development codes), and again work with other authorities to promote vegetative growth along the streams and river.

As can be seen in Figure 8, the section of the Jordan River within Taylorsville City boundaries

Salt Lake County—Stream Function Index (SFI)
Taylorsville City




Figure 9. Habitat Function—Riparian Density in Taylorsville City

4.2.7 Riparian Density in Taylorsville City

In addition to riparian width, the density of riparian vegetation is a strong indicator of overall stream health. This metric scores the percent coverage of the canopy, middle story, and understory to determine overall riparian density. As opposed to examining plant species, this metric assumes that the highest functioning riparian areas will have at least 80% coverage at all levels of the canopy.

As can be seen in Figure 9, the sections of the Jordan River within Taylorsville City boundaries scored 100 for riparian density. Therefore, it is recommended that Taylorsville City work to ensure that preserve the existing riparian density with the understanding that some restoration efforts may temporarily reduce this value in order

to re-establish native species in this section of the Jordan River. Additionally, it is recommended that Taylorsville City actively manage recreation areas to encourage riparian vegetation growth.



Salt Lake County—Stream Function Index (SFI) Taylorsville City




Figure 10. Hydraulics Functional Group Scores Countywide

4.3 HYDRAULICS FUNCTIONAL GROUP SCORE

The third watershed function examined for the purposes of the SFI was hydraulics function. This functional group is comprised of four metrics: floodplain development, floodplain connectivity, bank stability, and hydraulic alteration.

As can be seen in Figure 10, the majority of streams in Salt Lake County scored > 50 for the hydraulics function; however, an appropriate target for this functional group is closer to 75. Countywide, the streams with low hydraulics function scores were concentrated in the lower sections of the Wasatch Mountain streams. Namely, City Creek, Red Butte Creek, Emigration

Creek, and Parley's Creek showed low hydraulics function. This may be due to the highly developed nature of these streams and the extensive culverts on each of them.

The Jordan River within Taylorsville City boundaries showed hydraulics function scores between 60 and 69.9. The following information is provided to review hydraulics function metrics within Taylorsville City and identify opportunities to improve stream function by addressing concerns.




Figure 11. Hydraulics Function—Floodplain Development in Taylorsville City

4.3.1 Floodplain Development in Taylorsville City

The floodplain development metric evaluates the percent of impervious surface within the 100 year floodplain as defined by the FEMA Flood Insurance Program. For the purposes of the SFI, the target was that 100% of the floodplain be pervious, or free from development that would limit groundwater infiltration.

As can be seen in Figure 11, the majority of the Jordan River within Taylorsville City boundaries scored between 76 and 99 for floodplain development. A smaller section of the Jordan River in the central portion of Taylorsville City scored lower (between 51 and 75).

The challenge for Taylorsville City is to promote appropriate development in the river corridor and minimize development as much as possible. This could be done either through development codes or land use ordinances. Of note, the 2009 WaQSP recommends that all cities within Salt Lake County develop and adopt ordinances that will both limit impervious surface and development along stream and river corridors.

Salt Lake County—Stream Function Index (SFI)
Taylorsville City




Figure 12. Hydraulics Function—Floodplain Connectivity in Taylorsville City

4.3.2 Floodplain Connectivity in Taylorsville City

The floodplain connectivity metric is essentially a measure of stream entrenchment (or eroded streambed). Entrenchment disconnects the stream from its historic floodplain, lowers the water table, and increases the intensity of flood events. For the purposes of the SFI, floodplain connectivity was measured and scored against targets established by stream type (see SFI Main Report.) Any score falling within the appropriate entrenchment range for a stream type was given a score of 100. If the entrenchment ratio was outside the appropriate range, the reach was given a score of 0.

As can be seen in Figure 12, the Jordan River within Taylorsville City boundaries was seen to have appropriate entrenchment ratios (100). Therefore, it is recommended that Taylorsville City work closely with State agencies and Salt Lake County Flood Control to maintain existing entrenchment levels.

Salt Lake County—Stream Function Index (SFI)
Taylorsville City



WATER QUALITY
STEWARDSHIP PLAN




Figure 13. Hydraulics Function—Hydraulic Alteration in Taylorville City


4.3.3 Hydraulic Alteration in Taylorville City

Although bank stability is key to the hydraulics function of an urban stream, artificial bank configurations that reduce riparian and floodplain areas and the types of artificial materials used may cause stability and habitat problems. For the SFI, hydraulic alteration was evaluated as the percent of culverts and man-made bank stabilization structures and built with materials such as concrete riprap or gabion baskets within a reach. The percent was based on visual observation by field personnel and computer-aided mapping of culverts.

scored 100 for hydraulic alteration. Therefore, it is recommended that when upgrading bank stabilization structures or when new bank stabilization projects are necessary, Taylorville City partners with Salt Lake County Flood Control Division and State agencies to employ ecosystem restoration techniques.

As can be seen in Figure 13, the section of the Jordan River with Taylorville City boundaries

Salt Lake County—Stream Function Index (SFI) Taylorsville City



4.3.4 Bank Stability in Taylorville City

In addition to measuring the condition and frequency of man-made stability structures in Salt Lake County's streams and river, an established bank stability method was also employed to characterize overall stream stability.

The Pfankuch Stream Stability Evaluation protocol—developed for the U.S. Forest Service—was slightly modified for use on the urban streams of Salt Lake County. Although the Pfankuch rating is only one of the metrics contained in the SFI, it, in itself, examines 18 stream characteristics. This metric therefore contains abundant information that may be used in stream restoration and enhancement projects. “Hot spots”, or actively eroding sites, were also identified and mapped. Although the presence of a hot spot did not contribute directly to the score, they give an

indication of where to perhaps prioritize bank stabilization projects.

As can be seen in Figure 14, the southern portion of the Jordan River within Taylorville City boundaries scored “Good” for stream stability. The northern section of the river scored “Poor” for this metric. Although a score of “Excellent” would be ideal, a “Good” score is considered acceptable. It is therefore recommended that Taylorville work to maintain the existing stability in the southern section of the Jordan River along it's boundary by limiting development adjacent to the stream and seeking to improve stability as concerns arise. It is also recommended that Taylorville City work with local land owners, State agencies, Salt Lake County Flood Control, and nonprofit organizations to identify opportunities for restoration efforts in the northern section of the Jordan River.

Salt Lake County—Stream Function Index (SFI)
Taylorsville City




Figure 15. Social Functional Group Scores Countywide

4.4 SOCIAL FUNCTIONAL GROUP SCORE

Social watershed function was measured by examining recreational facilities: management, aesthetics, location, Americans with Disabilities Act (ADA) compatibility, restroom facilities, trail connectivity, and resource compatibility.

Social function is probably the most difficult function to measure because there is a broad range of preferences by recreationists for different types of facilities. Therefore, the SFI focused on assessing the availability of all types of recreation facilities along the waterways, the minimum requirements for a positive user experience, and impact that the use of those facilities may have on the stream ecosystem. Although recreation may

have detrimental impacts on stream and river corridors, it is the opinion of Salt Lake County staff that the best way to promote stewardship of local resources is to provide appropriate facilities and access.

As can be seen in Figure 15, the section of the Jordan River flowing through Taylorsville City scored between 60 and 69.9 for overall social function. In order to encourage appropriate access to the river in Taylorsville, the City is encouraged to work with local property owners to identify opportunities for enhanced recreational access.

Salt Lake County—Stream Function Index (SFI)
Taylorsville City




Figure 16. Ecosystem Health Index (EHI) Final Score 2009

5.0 ECOSYSTEM HEALTH INDEX (EHI) - TAYLORSVILLE CITY

In order to determine the physical, chemical, and biological health of streams in Salt Lake County, the County has developed an Ecosystem Health Index (EHI) score. This score is meant to reflect the ecological health of the stream. Although the County's position is to promote responsible and appropriate recreational access along the stream corridors, it is also understood that recreational activities may counteract ecological function. Therefore, it is important to examine the combined EHI score outside of the overall Stream Function Index (SFI) score which includes the Social Function.

As can be seen in Figure 16, the Jordan River scored between 60 and 69.9 within Taylorsville City boundaries. In review of the EHI components, it appears that these scores are largely driven by low water quality and habitat scores. To address these concerns, it is recommended that Taylorsville City partner with adjacent cities and other agencies to complete and implement the Jordan River TMDL in an efficient and timely manner. It is also recommended that Taylorsville City seek partners and explore river restoration efforts. Additionally, it is recommended that Taylorsville City establish zoning ordinances and/or regulations that will limit development along the river.

Salt Lake County—Stream Function Index (SFI)
Taylorsville City




Figure 17. Stream Function Index (SFI) Final Score 2009

6.0 STREAM FUNCTION INDEX (SFI) - TAYLORSVILLE CITY

To include social/recreational functions in the overall SFI score, Salt Lake County combined the EHI with social scores.

As can be seen in Figure 17, the Jordan River had an SFI score between 60 and 69.9 within Taylorsville City boundaries. In review of the SFI components, it appears that these scores are again largely driven by low water quality and habitat scores along the Jordan River.

To address these concerns, it is recommended that Taylorsville City partner with adjacent cities and other agencies to complete and implement

the Jordan River TMDL in an efficient and timely manner. It is also recommended that Taylorsville City seek partners and explore river restoration efforts. Additionally, it is recommended that Taylorsville City establish zoning ordinances and/or regulations that will limit development along the river. It is also recommended that Taylorsville City make efforts to include recreational facilities in development along the Jordan River.



7.0 IMPLEMENTATION

Because many of the recommendations included in this document suggest stream/river restoration efforts, this section is written to provide some general guidelines/suggestions with such projects.

7.1 SITE IDENTIFICATION

Salt Lake County encourages local cities to consult the data collected as part of the SFI effort to identify appropriate restoration sites. In addition to the GIS data that each city will be provided, Salt Lake County staff are available for consultation and assistance with grant application efforts.

7.2 PLAN DEVELOPMENT

Salt Lake County has used an “Emergent Bench” design for restoration projects along the Jordan River (Figure 18). This design is appropriate for

reaches with large easements/access. If easements are not available, other designs may need to be developed. Currently, Salt Lake County is working to develop ideas for entrenched, urban reaches.

7.3 FUNDING

As with most municipal functions, a major hurdle to stream/river restoration projects is funding. Some municipalities have elected to use stormwater utility fees or bond efforts to fund such projects. However, the majority of projects that have been completed in Salt Lake County have relied heavily on Federal grants. Fortunately, numerous Federal grants are available to support stream restoration efforts. However, the cost of site identification and plan development usually fall to the sponsoring agency.

Although application deadlines and typical amounts awarded vary greatly, there are some common characteristics of successful grant applications:




Figure 18. Diagram of Emergent Bench design used along the Jordan River

- A clear, precise workplan
- Demonstrated involvement of many partners
- Inclusion of a monitoring effort
- Strong financial match

A list of some grants that may be appropriate are provided in Table 3, Grants for Stream and River Restoration Projects.

7.4 PLAN IMPLEMENTATION

With robust planning, established partnerships, and sufficient funding, stream and river restoration efforts may be highly successful. However, some pitfalls do exist. Things to be aware of during a stream restoration effort:

- Flow diversions may occur unexpectedly. Please assure that all permits (namely stream alteration and flood control permits) have been acquired and appropriate entities notified to avoid the unexpected destruction of restoration work.
- Order your plant and rock material early as many of these materials are in high demand.
- Notify the public. Although stream and river restoration efforts are a great benefit to the

local stream health, the process of restoration may at times appear destructive. Post notices explaining the project in order to prevent public misunderstanding.

- Allow enough time. As with most projects, stream and river restoration projects may take longer than expected. Be sure to plan for unexpected delays in your scheduling.
- We're not the only ones that love trees. In many of the restoration efforts that Salt Lake County has overseen, beaver activity has been highly destructive. Be sure to consult local experts to prevent the destruction of your newly planted trees.

7.5 POST-CONSTRUCTION

One of the most important components of a successful stream or river restoration project is the long-term maintenance of the restoration site. Especially in the arid Salt Lake Valley, be sure to plan for irrigation of planted vegetation, and weed control to assure that the monies spent on the restoration project are used to their fullest extent; budgeting for a two-year establishment period is ideal.



Example of before (above) and after (right) river restoration project completed in 2009 using Emergent Bench model along the Jordan River. This site in Riverton will be irrigated for 2 years to establish vegetation.



GRANT	SPONSOR	ELIGIBLE	TYPES OF PROJECTS	MATCH	\$ RANGE	DEADLINE	MORE INFORMATION
Targeted Watershed Grant	Environmental Protection Agency (EPA)	States, local governments, public and private nonprofit institutions/ organizations, federally recognized Indian tribal governments, U.S. territories or possessions, and interstate agencies.	<p>Eligible Activities Activities that will result in the protection, and restoration of a watershed that incorporates a watershed-based approach, and meets the prescribed criteria.</p> <p>Ineligible</p> <ul style="list-style-type: none"> - Development of TMDLs - Phase II Stormwater Projects - Construction of buildings or major structures - Purchase of equipment of machinery <p>NOTE: Watershed nominations must be submitted by either a Governor or a Tribal Leader.</p>	25% Non-federal match	2005 Grants ranged from \$600,000 to \$850,00	Typically October through November	http://www.epa.gov/twg
Environmental Education Grants	Environmental Protection Agency (EPA)	Local education agency, state education or environmental agency, college, or university, not-for-profit organization as described in section 501(C)(3) of the Internal Revenue Code, noncommercial educational broadcasting entity, tribal education agency (which includes school and community colleges controlled by an Indian tribe, band, or nation)	Environmental education projects that enhance the public's awareness, knowledge, and skills to help people make informed decisions that affect environmental quality.	25% Non-federal match	Applications may be up to \$50,000; however, typical awards are between \$15,000 and \$20,000	Typically in December	http://www.epa.gov/enviroed/grants.html
Aquatic Ecosystem Restoration (Section 206 of WRDA)		Nonprofit Groups, Conservation District, Water and Wastewater Utilities, Local Government, State/ Territorial Agency	Financial and technical assistance to promote the conservation and improvement of soil, water, air, energy, plant and animal life, and other conservation purposes on Tribal and private working lands.	35% Non-federal match	Typical awards are ~\$300,000	None - these allocations are through Section 206 of the WRDA	www.usace.army.mil/cw/
Conservation Security Program	Note: Upper Weber has received this	The agricultural operation must be privately owned land or Tribal land, the majority of which must be located within a selected priority watershed. The applicant must be in compliance with highly erodible and wetland compliance provisions, have an active interest in the agricultural operation, and have control of the land for the life of the contract. The applicant must share in the risk of producing any crop or livestock and be entitled to a share in the crop or livestock marketed from the		None required	Not available; however, in FY 2007 this program was awarded \$259 Million	1. The CSP sign-up will be offered in selected priority watersheds across the Nation. 2. Producers completed a self-assessment to determine eligibility. 3. Eligible producers within these watersheds submit an application. 4. Base on the application, description of conservation activities, and a follow up interview, the Natural Resources Conservation Service	www.nrcs.usda.gov/programs/csp

Table 3. Grants for Stream and River Restoration Projects

GRANT	SPONSOR	ELIGIBLE	TYPES OF PROJECTS	MATCH	\$ RANGE	DEADLINE	MORE INFORMATION
Conservation Security Program - Continued		operation. There are certain tier eligibility and contract requirements, as well: -For Tier I, the producer must have addressed soil quality and water quality for eligible land uses on part of the agricultural operation prior to application. -For Tier II, the producer must have addressed soil quality and water quality for eligible land uses on the entire agricultural operation prior to application and agree to address one additional resource concern by the end of the contract period. -For Tier III, the producer must have addressed all resource concerns to a resource management system level for all eligible land uses on the entire agricultural operation and adequately treat riparian zones before application into the program.				(NRCS) will determine which program tier and enrollment category are available for the applicant.	
Environmental Quality Incentives Program (EQIP)		Business, Community/Watershed Group, Nonprofit Groups, Educational Institution, Private Landowner, Water and Wastewater Utilities, State/Territorial Agency, Tribal Agency, Agricultural producers who face serious threats to soil, water, and related natural resources, or who need assistance with complying with Federal and State environmental laws. A participant may be an owner, landlord, operator, or tenant of eligible agricultural lands. Limited resource producers, small-scale producers, producers of minority groups, Federally recognized Indian tribal governments, Alaska natives, and Pacific Islanders are encouraged to apply.	These contracts provide incentive payments and cost-shares to implement conservation practices. Persons who are engaged in livestock or agricultural production on eligible land may participate in the EQIP program.	Typically 25 to 50%	Limited to \$10,000 per person per year and to \$50,000 over the length of the contract. Not available in FY 2007 this program was awarded \$739 Million		http://www.nrcs.usda.gov/programs/eqip
Five-Star Restoration Program		Business, Community/Watershed Group, Nonprofit Groups, Educational Institution, Private Landowner, Conservation District, Water and Wastewater Utilities, Local Government, State/Territorial Agency, Tribal Agency		Typical projects include at least five diverse partners. Most partnerships contribute more than \$40,000 for every \$10,000 Five Star grant.	Typically range between \$5,000 and \$20,000	Typically in February or March	http://www.epa.gov/owow/wetlands/restore/5star/index.html

Table 3. Grants for Stream and River Restoration Projects (continued)

GRANT	SPONSOR	ELIGIBLE	TYPES OF PROJECTS	MATCH	\$ RANGE	DEADLINE	MORE INFORMATION
Land and Water Conservation Fund (Outdoor Recreation, Acquisition, Development and Planning Grants)	National Park Service (NPS)	Local Government, State/Territorial Agency, Tribal Agency			Typically range between \$1,000 and \$3 million - median is \$150,000		http://www.nps.gov/nrc/programs/wcwf/
Natural Resources Conservation Service: Conservation on Private Lands	National Fish and Wildlife Foundation (NFWF)	Community/Watershed Group, Nonprofit Groups, Educational Institution, Conservation District, Local Government, State/Territorial Agency, Tribal Agency, Federal Agency	Grants are awarded to projects that: (1) address priority actions promoting fish and wildlife conservation and the habitats on which they depend; (2) work proactively to involve other conservation and community interests; (3) leverage available funding; and (4) evaluate project outcomes.	NFWF funds must be matched on at least a 1:1 basis, although 2:1 is encouraged, and higher ratios are more competitive.	Typically range between \$10,000 and 150,000 - median is \$60,000	Varies each year.	http://www.nfwf.org/AM/Template.cfm?Section=Home
Nonpoint Source Implementation Grants (319 Programs)	Environmental Protection Agency (EPA) through the Utah Division of Water Quality	Business, Community/Watershed Group, Nonprofit Groups, Educational Institution, Conservation District, Local Government, State/Territorial Agency, Tribal Agency, Federal Agency	Restoration, Information & Education, Planning, TMDL implementation	States required to provide 40% non-Federal match for whole grant. Recipients within state typically required to provide 40% match for each project, but this may be negotiable with a given state.	Varies		Mike Reichert; Utah Division of Water Quality (DWQ)
North American Wetlands Conservation Act Grants Program	United States Fish and Wildlife Service (USFWS)	Business, Nonprofit Groups, Private Landowner, Local Government, State/Territorial Agency, Federal Agency	Long-term protection, restoration, and/or enhancement of wetlands and associated uplands habitats.	Cost-share partners must match grant funds 1:1 with U.S. non-federal dollars	Funding amounts vary; however in 2007 this program was awarded 39.4 Million	Typically in early spring (March)	http://www.fws.gov/birdhabitats/Grants/NAWC/index.shtml
Not-for-Profit Acid Mine Drainage Reclamation	U.S. Department of the Interior Office of Surface Mining, Division of Reclamation Support	Community/Watershed Group, Nonprofit Groups, Conservation District	Support the efforts of local not-for-profit organizations, especially watershed groups, to complete construction projects designed to clean streams impacted by Acid Mine Drainage	Partners are encouraged to make monetary contributions or provide in-kind services; however, a specific match is not specified.	Typically range between \$25,000 and \$150,000 - median is \$50,000	Applications will be accepted until all available funds have been awarded	http://www.osmre.gov/osnaml.htm

Table 3. Grants for Stream and River Restoration Projects (continued)

GRANT	SPONSOR	ELIGIBLE	TYPES OF PROJECTS	MATCH	\$ RANGE	DEADLINE	MORE INFORMATION
Partners for Fish and Wildlife Program	U.S. Department of the Interior, U.S. Fish and Wildlife Service Branch of Habitat Restoration, Division of Fish and Wildlife Management and Habitat Restoration	Business, Community/Watershed Group, Nonprofit Groups, Educational Institution, Private Landowner, Conservation District, Local Government, Tribal Agency	The partners for Fish and Wildlife Program provides technical and financial assistance to private landowners to restore fish and wildlife habitats on their lands.	Typically an applicant contributes 50% of the total project cost through matching funds or in-kind services but this amount is negotiable.	Typically range between \$300 and \$25,000 - median is \$25,000	Funds available year -round	http://ecos.fws.gov/partners/viewContent.do?viewPage=home
Urban and Community Forestry Challenge Cost-Share Grants	USDA Forest Service	Business, Community/Watershed Group, Nonprofit Groups, Educational Institution, Conservation District, Water and Wastewater Utilities, Local Government, State/Territorial Agency, Tribal Agency	The program works to achieve a number of goals, including (1) effectively communicating information about the social, economic, and ecological values of urban and community forests; (2) involving diverse resource professionals in urban and community forestry issues; and (3) supporting a holistic view of urban and community forestry. In particular, the program supports an ecosystem approach to managing urban forests for their benefits to air quality, stormwater runoff, wildlife and fish habitat, and other related ecosystem concerns.	All grant funds must be matched at least equally (dollar for dollar) with non-federal source funds.	Typically range between \$3,000 and \$250,000 - median is \$125,000	The annual Request for Pre-Proposals is released the first week in September. Pre-proposals are due the second Tuesday of November	http://www.freelink.org/nucfac
Water 2025 Challenge Grant Program	Bureau of Reclamation, Office of Program & Policy Services	Nonprofit Groups, Educational Institution, Conservation District, Water and Wastewater Utilities, Local Government, State/Territorial Agency, Tribal Agency	The goal of Water 2025 is to prevent crises and conflict over water in the western United States. The Challenge Grant Program is administered by the Bureau of Reclamation and is designed to contribute to this goal by providing 50% funding for projects that will conserve water, increase water use efficiency, or enhance water management, using advanced technology, improvements to existing facilities, and water banks and markets.	A match is required, but the % is not specified.	Typically range between \$19,000 and \$300,000 median is \$140,000	Visit the Department of the Interior Water 2025 website, www.doi.gov/water2025/ , for current information on any upcoming RFP dates and deadlines	http://www.doi.gov/water2025
Water Resources Research National Competitive Grants Program	U.S. Geological Survey	Educational Institution	Proposals are sought in not only the physical dimensions of supply and demand, but also quality trends in raw water supplies, the role of economics and institutions in water supply and demand, institutional arrangements for tracking and reporting water supply and availability, and institutional arrangements for coping with extreme hydrologic conditions.	A match is required, but the % is not specified.	Typically range between \$5,000 and \$250,000 - median is \$120,000	February 16, 2007 (for investigations); March 2, 2007 (for institutes)	http://water.usgs.gov/wrri/institutes.html

Table 3. Grants for Stream and River Restoration Projects (continued)

GRANT	SPONSOR	ELIGIBLE	TYPES OF PROJECTS	MATCH	\$ RANGE	DEADLINE	MORE INFORMATION
Watershed Protection and Flood Prevention Program	USDA	Conservation District, Local Government, State/Territorial Agency, Tribal Agency	Projects related to watershed protection, flood mitigation, water supply, water quality, erosion and sediment control, wetland creation and restoration, fish and wildlife habitat enhancement, agricultural water conservation, and public recreation are eligible for assistance. Technical and financial assistance is also available for planning new watershed surveys.	Approximately 75%	Typically range between \$5,000 and \$2.16 Million - median is \$650,000	Eligible project sponsors may submit formal requests for assistance to the NRCs state conservationists in each state at any time.	http://www.nrcs.usda.gov/programs/watershed/
Wetlands Program Development Grants	EPA	Nonprofit Groups, Local Government, State/Territorial Agency, Tribal Agency	The EPA's Wetland Program Development Grants are intended to encourage comprehensive wetlands program development by promoting the coordination and acceleration of research, investigations, experiments, training, demonstrations, surveys, and studies relating to the causes, effects, extent, prevention, reduction, and elimination of water pollution. Projects build the capacity of states, tribes and local governments to effectively protect wetland and riparian resources. Projects funded under this program support the initial development of a wetlands protection, restoration or management program or support enhancement/refinement of an existing program.	25% Non-federal match	Typically range between \$11,000 and \$500,000 - median is \$250,000	Deadlines are determined annually and vary from region to region.	http://www.epa.gov/owow/wetlands/grantguidelines/
Wetlands Reserve Program	USDA - NRCS	Business, Community/Watershed Group, Nonprofit Groups, Educational Institution, private Landowner, Conservation District, Water and Wastewater Utilities, Local Government, State/Territorial Agency, Tribal Agency	Through this voluntary program, the USDA Natural Resources Conservation Service (NRCS) provides landowners with financial incentives to restore and protect wetlands in land.	For restoration cost-share agreements and 30 year easement participants, up to 25% of the cost of restoring the acreage must be provided.		Applications are accepted year-round.	http://www.nrcs.usda.gov/
Wildlife Habitat Incentives Program	USDA - NRCS	Nonprofit Groups, Private Landowners	The Wildlife Habitat Incentive Program (WHIP) is a voluntary program for people who want to develop and improve wildlife habitat on private lands. It provides both technical assistance and cost sharing to help establish and improve fish and wildlife habitat. Participants work with USDA's Natural Resources Conservation Service to prepare a wildlife habitat development plan in consultation with a local conservation district. The plan describes the landowner's goals for improving wildlife habitat, includes a list of practices and a schedule for installing them, and details the steps necessary to maintain the habitat for the life of the agreement.	25% Non-federal match	Not available; however, in FY 2007 this program was awarded \$259 Million	Continuous sign-up process	http://www.nrcs.usda.gov/programs/whip/

Table 3. Grants for Stream and River Restoration Projects (continued)